

JSCE Guidelines for Concrete No.8

RECOMMENDATIONS FOR SHOTCRETING
(Draft)

Contents

Part 1 “Tunnels by the NATM”

Chapter 1 General..... 1

1.1 Scope 1

1.2 General 3

1.3 Definitions 9

Chapter 2 Performance establishment..... 10

2.1 General 10

2.2 Performance establishment for NATM tunnels 12

2.3 Performance establishment for shotcrete..... 12

2.3.1 General 12

2.3.2 Mechanical performance 14

2.3.2.1 Design strength..... 14

2.3.2.2 Initial strength..... 15

2.3.2.3 Bending toughness 17

Chapter 3 Performance verification..... 19

3.1 General 19

3.2 Verification for tunnels by the NATM..... 19

3.3 Verification for shotcrete 20

3.3.1 General 20

3.3.2 Verification for mechanical performance 22

3.3.2.1 Verification for design strength 22

3.3.2.2 Verification for initial strength 23

3.3.2.3 Verification for bending toughness..... 24

Chapter 4 Construction planning 25

4.1 General 25

4.2 Construction planning for an entire tunnel construction project 26

4.3 Construction planning for shotcreting 27

4.3.1 General 27

4.3.2 Shotcreting process..... 29

4.3.3 Shotcreting procedure..... 32

4.3.4 Gunning operation..... 33

4.3.5	Nozzleman.....	33
4.4	Confirmation of construction planning for shotcreting	34
4.4.1	General	34
4.4.2	Confirmation of placing performance	36
4.4.2.1	Confirmation of pumpability.....	36
4.4.2.2	Confirmation of the rebound ratio.....	38
4.4.2.3	Confirmation of dust concentration.....	41
4.5	Modification of construction planning	44

Chapter 5 Materials and mix proportion design..... 45

5.1	General	45
5.2	Shotcrete materials	45
5.2.1	General	45
5.2.2	Cement	46
5.2.3	Water	46
5.2.4	Aggregates.....	46
5.2.5	Set accelerating agent.....	47
5.2.6	Chemical admixtures.....	48
5.2.7	Mineral admixtures.....	49
5.2.8	Reinforcement	50
5.3	Mix proportion design	51
5.3.1	General	51
5.3.2	Maximum aggregate size.....	52
5.3.3	Unit water content and slump.....	52
5.3.4	Water-cement ratio and unit cement content	53
5.3.5	Sand-coarse aggregate ratio.....	53
5.3.6	Dosage of accelerator	54
5.3.7	Dosage of admixtures and unit content	54
5.3.8	Fiber content.....	54

Chapter 6 Production and construction equipment 56

6.1	General	56
6.2	Production equipment.....	56
6.2.1	Storage equipment.....	56
6.2.2	Measurement equipment and auxiliary equipment.....	57
6.2.3	Mixing equipment	59
6.3	Production	60
6.3.1	Measuring.....	60
6.3.2	Mixing.....	61
6.4	Shotcreting equipment.....	64
6.4.1	General	64
6.4.2	Shotcreting machine	65
6.4.3	Remote shotcreting equipment.....	66
6.4.4	Accelerator dispensers.....	67
6.4.5	Miscellaneous equipment.....	67
6.4.6	Newly developed shotcreting equipment	68

Chapter 7	Construction	69
7.1	General	69
7.2	Storage of reinforcements.....	69
7.3	Placement of wire fabric.....	70
7.4	Delivery	70
7.5	Surface protection.....	71
7.6	Shotcreting	72
7.6.1	General	72
7.6.2	Velocity and pressure at the nozzle	72
7.6.3	Delivery distance.....	73
7.6.4	Angle and distance of gunning.....	74
7.6.5	Buildup of a shotcrete layer.....	75
7.6.6	Placement of steel supports	76
7.6.7	Finishing surface of shotcrete.....	77
7.7	Special application	77
7.7.1	Shotcreting on water ingress	77
7.7.2	Long delivery	80
7.7.3	Long transport and length of wait after mixing.....	80
7.7.4	Execution of shotcreting for vertical tunnels or diagonal tunnels	81
7.8	Safety and health	81
7.8.1	General	81
7.8.2	Protection against dust.....	82
7.9	Curing.....	83
7.10	Construction control.....	83
7.10.1	General	83
7.10.2	Control of placing performance.....	84
Chapter 8	Inspection	85
8.1	General	85
8.2	Inspection planning	87
8.3	Acceptance inspection of materials	88
8.3.1	Concrete materials.....	88
8.3.2	Reinforcements.....	89
8.4	Inspection of production equipment.....	89
8.5	Inspection of base concrete	90
8.6	Inspection of shotcrete.....	90
8.7	Inspection of application thickness	92
8.8	Inspection records.....	92
Chapter 9	Construction records	93

Part 2 “Slope Stabilization”

Chapter 1	General	95
1.1	Scope	95
1.2	Types of shotcreted slope structures	100
1.3	Shotcrete for slope stabilization	101
1.4	Definitions	103
Chapter 2	Performance establishment	104
2.1	General	104
2.2	Performance establishment for shotcreted slope structures	104
2.2.1	General	104
2.2.2	Safety	106
2.2.3	Performance for hazards to third parties	107
2.2.4	Performance for aesthetic appearance and landscape	107
2.2.5	Durability	108
2.3	Performance establishment for shotcrete for slope stabilization	108
2.3.1	General	108
2.3.2	Mechanical performance	109
2.3.3	Durability	110
Chapter 3	Performance verification	111
3.1	General	111
3.2	Verification for shotcrete structures	111
3.2.1	General	111
3.2.2	Verification for safety	112
3.2.3	Verification for hazards to third parties	112
3.2.4	Verification for aesthetic appearance and landscape	113
3.2.5	Verification for durability	113
3.3	Performance verification of shotcrete members	114
3.3.1	Verification for mechanical performance	114
3.3.2	Validation of endurance performance	115
Chapter 4	Construction planning	119
4.1	General	119
4.2	Construction planning for a slope shotcrete project	119
4.3	Construction planning for a shotcreted slope	121
4.4	Determination of shotcrete processes	124
4.5	Confirmation of construction planning for slope shotcrete projects	125
4.5.1	General	125
4.5.2	Confirmation of placing performance	126

4.6	Modification of construction planning	129
-----	---	-----

Chapter 5 Materials and mix proportion design..... 130

5.1	General	130
5.2	Shotcrete materials	130
5.2.1	General	130
5.2.2	Cement	131
5.2.3	Water	131
5.2.4	Aggregates.....	132
5.2.5	Admixtures	133
5.3	Reinforcement	134
5.3.1	General	134
5.3.2	Selection of reinforcements.....	134
5.3.3	Storage of reinforcements.....	136
5.4	Mix proportion design	136
5.4.1	General	136
5.4.2	Required average strength	136
5.4.3	Mix proportion design	138

Chapter 6 Production and construction equipment 142

6.1	General	142
6.2	Production equipment.....	142
6.2.1	Storage equipment.....	142
6.2.2	Measurement equipment	143
6.3	Mixer, gun and accessories.....	144
6.4	Production	146
6.4.1	Measuring and preparation of materials	146
6.4.2	Mixing	146

Chapter 7 Construction 149

7.1	General	149
7.2	Preparation for shotcreting	150
7.3	Assembly of reinforcement, formwork and mesh	152
7.4	Shotcreting	153
7.5	Safety and health	155
7.6	Curing.....	155
7.7	Placement control.....	155
7.7.1	General	155
7.7.2	Items and methods for construction management	156

Chapter 8 Inspection..... 158

8.1	General	158
8.2	Inspection planning	159

8.3	Acceptance inspection of materials	160
8.4	Inspection of production.....	160
8.4.1	General	160
8.4.2	Inspection of production equipment.....	161
8.4.3	Inspection of production processes	161
8.5	Inspection of reinforcement assembly	162
8.6	Inspection of in-place shotcrete.....	163
8.6.1	General	163
8.6.2	Inspection of in-place shotcrete.....	164
8.6.3	Quality inspection of in-place shotcrete	165
8.7	Inspection of shotcreted slope structure	166
8.8	Inspection records.....	166

Chapter 9 Construction records and maintenance 168

Part 3 “Repair and Strengthening”

Chapter 1 General..... 171

1.1	Scope	171
1.2	General	172
1.3	Definitions.....	175

Chapter 2 Performance establishment..... 176

2.1	General	176
2.2	Performance establishment for concrete structures	177
2.3	Performance level required of a structure	178
2.4	Performance establishment for shotcrete.....	180
2.4.1	General	180
2.4.2	Mechanical performance	182
2.4.3	Cracking resistance.....	183
2.4.4	Durability	185
2.4.5	Spalling resistance.....	186
2.4.6	Performance for aesthetic appearance and landscape.....	187

Chapter 3 Performance verification..... 188

3.1	General	188
3.2	Verification for the structures repaired or strengthened with shotcrete.....	188
3.3	Verification for shotcrete	189
3.3.1	General	189
3.3.2	Verification for mechanical performance	190
3.3.3	Verification for cracking resistance	192
3.3.4	Verification for durability	194
3.3.5	Verification for spalling resistance	196

3.3.6	Verification for aesthetic appearance and landscape	196
Chapter 4	Design and construction planning	198
4.1	General	198
4.2	Selection of construction processes.....	199
4.2.1	Selection of a repair and strengthening process	199
4.2.2	Selection of shotcrete processes	202
4.3	Repair design.....	203
4.3.1	General	203
4.3.2	Procedures for repair design.....	205
4.4	Strengthening design	206
4.4.1	General	206
4.4.2	Procedures for strengthening design	208
4.5	Planning of repair and strengthening projects.....	209
4.5.1	General	209
4.5.2	Confirmation of the shotcreting planning.....	210
Chapter 5	Materials and mix proportion design.....	211
5.1	General	211
5.2	Shotcrete materials	211
5.2.1	General	211
5.2.2	Cement	213
5.2.3	Water	213
5.2.4	Aggregate	213
5.2.5	Fibers.....	214
5.2.6	Admixtures.....	215
5.2.7	Premixed materials.....	217
5.3	Basic concept of mix proportion design.....	220
5.3.1	General	220
5.3.2	Mix proportion of shotcretes	220
5.3.3	Mix proportion of premixed materials	221
Chapter 6	Construction	223
6.1	General	223
6.2	Pre-survey of existing concrete structure	224
6.3	Preparatory work	225
6.4	Removal of deteriorated concrete.....	226
6.5	Preparation of concrete surface	227
6.6	Corrosion protection of reinforcing bars	228
6.7	Shotcreting	229
6.7.1	General	229
6.7.2	Dry-mix process	231
6.7.3	Wet-mix process	233
6.8	Safety and health	235

6.9	Finishing and curing.....	236
6.10	Placement control.....	236
6.10.1	General	236
6.10.2	Control of shotcreting.....	237
6.11	Use of another process with the shotcreting method.....	238
Chapter 7 Inspection.....		240
7.1	General	240
7.2	Inspection planning	241
7.3	Acceptance inspection of materials.....	242
7.4	Inspection of equipment.....	243
7.5	Inspection of production process.....	244
7.6	Inspection of shotcrete placement.....	245
7.7	Inspection of reinforcement assembly.....	247
7.8	Inspection of in-place shotcrete.....	247
7.8.1	General	247
7.8.2	Inspection of in-place shotcrete.....	248
7.8.3	Quality inspection of in-placed shotcrete.....	249
7.9	Inspection of structure repaired and strengthened with shotcrete	251
Chapter 8 Maintenance.....		252
8.1	Fundamental considerations in maintenance.....	252
Chapter 9 Construction records		254
9.1	General	254
9.2	Work records	254
9.2.1	General	254
9.2.2	Inspection records.....	255
9.3	Maintenance records.....	256

Part 4 “JSCE Standards for Sprayed Concrete”

JSCE-D 102-2005 Specification for Set Accelerating Agent for Sprayed Concrete (Mortar) (Draft)	257
---	------------

JSCE-F 561-2005 Method of Making Specimens for Compressive Strength Tests of Sprayed Concrete (Mortar) (Draft)	268
---	------------

JSCE-F 562-2005 Method of Making Specimens for Durability Tests of Sprayed Concrete (Mortar) (Draft)	271
JSCE-F 563-2005 Test Method for Rebound Percentage of Sprayed Concrete (Mortar) (Draft)	274
JSCE-F 564-2005 Test Method for Dust Concentration in Air During Spraying Concrete (Mortar) (Draft)	279
JSCE-F 565 2005 Test Method for Mechanical Properties, Spraying Performance and Durability of Sprayed Concrete (Mortar) (Draft)	284
JSCE-F 566-2005 Method of Making Specimens of Bond Strength Tests of Sprayed Concrete (Mortar) for Repairing and Strengthening (Draft)	289
JSCE-G 561-2005 Test Method for Early Strength of Sprayed Concrete (Mortar) by Pull-out Method (Draft)	291
JSCE-G 562-2005 Test Method for Early Strength of Sprayed Concrete (Mortar) Using Prism Specimens (Draft)	295
JSCE-G 563-2005 Test Method for Strength of Sprayed Concrete (Mortar) for Repairing and Strengthening Using Prism Specimens (Draft)	298
JSCE-G 564-2005 Test Method for Length Change of Sprayed Concrete (Mortar) for Repairing and Strengthening (Draft)	301